

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21489-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 17-25S-9W
2946 feet from S Section Line, 2531 feet from E Section Line
Lease Name: ROARK Well #: 17-7
County: RENO Total Vertical Depth: 3978 feet

Operator License No.: 32204
Op Name: REDLAND RESOURCES, INC.
Address: 6001 NW 23RD ST.
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3978		125 SX CMT
SURF	8.625	330		250 SX CMT

\$ 129.29

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2006 8:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN THROWER Company: REDLAND RESOURCES, INC. Phone: (405) 789-7104

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DOUG LOUIS Witness Type: PARTIAL
Date/Time Plugging Completed: 03/28/2006 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

CIBP set at 3600' with 4 sacks of cement on top of plug. Shot casing at 2700' and pulled to 1450' and spotted 35 sacks of cement. Pulled casing to 816' and spotted 35 sacks of cement. Pulled casing to 380' and circulated 130 sacks of cement to surface.

60/40 posmix with 4% gel
Allied Cement #23097

Perfs:

Top	Bot	Thru	Comments
3890	3926		
3680	3688		

RECEIVED
KCC DISTRICT #2
APR - 6 2006
WICHITA, KS

RECEIVED
APR 19 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE 4-19-06

WE. NO. 20060615172

PCT