

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01332-00-00  
Spot: SESW Sec/Twnshp/Rge: 33-8S-16W  
660 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: ADAMS B Well #: 1  
County: ROOKS Total Vertical Depth: 3375 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3375	0	w/100 sxs cmt
SURF	8.625	183	0	w/150 sxs cmt

\$ 109.69

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2006 9:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 300 sxs cement and 500# hulls.  
Plug with tubing.  
Perforate at 850' and 1250'.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/05/2006 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Squeezed at 2527' w/100 sxs.  
Ran tubing to 2170' - spotted 75 sxs cement with 200# hulls.  
Pulled tubing to 1200' - circulated with 100 sxs cement with 200# hulls.  
Pulled all tubing and squeezed 5 1/2" casing with 15 sxs cement and 100# hulls.  
Max. P.S.I. 600#. S.I.P. 500#.  
Tied to annulus and squeezed 50 sxs cement.  
Max. P.S.I. 250#. S.I.P. 100#.  
Total of 240 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3234	3247		
3223	3226		
3205	3209		
3098	3102		
3080	3086		

**INVOICE**  
DATE 4-20-06  
TEL NO. 2006061514

Remarks: ALLIED CEMENTING COMPANY. SMOKY HILL TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger D. Moses  
(TECHNICIAN)

RECEIVED

APR 20 2006

KCC WICHITA

Form CP-2/3

APR 17 2006

PCT

R A COMEAU & MURFIN DR LG

#1 ADAMS 'B'

33-8-16W  
C SE SW

Contr. MUREIN DR LG

ROOKS

County

E-2004 RB Comm

Comp. 9-22-61

IP 25 BOPD/LANS

Tops	Depth	Datum
ANH	1253	+751
TOP	2855	-851
HFER	3075	-1071
TOR	3094	-1090
LANS	3115	-1111
B/KC	3345	-1341
TD	3375	-1371

Casing  
8" 183  
5" 3375

PERF 24/3080-86: 12/3098-3102:  
16/3205-3209: 12/3223-26: 12/  
3234-37: ACID 1000: SWB 8 BOPH

LATON POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

WADICER