

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-45473-00-00
Spot: S2NWSW Sec/Twnshp/Rge: 32-14S-13W
3630 feet from N Section Line, 660 feet from W Section Line
Lease Name: ELRLICH Well #: 3
County: RUSSELL Total Vertical Depth: 2967 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	2873	0	150 SX CMT
SURF	10.75	314	0	150 SX CMT

96.43

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/14/2006 9:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: MICHAEL A MCGLOCKLIN Company: SHIELDS OIL PRODUCERS INC. Phone: (785) 483-3141

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/14/2006 11:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 2000'.
Pumped 100 sxs 60/40 pozmix - 10% gel cement with 250# hulls.
Pulled to 1000' and circulated with 75 sxs cement with 200# hulls.
POOH. Tied onto casing and pumped 100 sxs cement with 100# hulls.
Max. P.S.I. 800#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
2872	2967		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

INVOICED
DATE 4-20-06
TIME 20060615:17

District: 04

110

Signed _____

Case Morris

(TECHNICIAN)

RECEIVED

APR 20 2006

KCC WICHITA

Form CP-2/3

APR 17 2006

PET

1173

SKELLY OIL CO.

#3

EHRlich

32-14-13W
CS2 NW SW

Contr. _____ RUSSELL _____ County

E 1723 C 2-23-41 Comp. 3-22-41 IP 2218 BOPD Deptho

Tops	Depth	Datum	Casing
ANHY	685		10" 314 6" 2873
TOP	2570		
DODGE	2809		
LANS	2855		
TD	2967		

Pay 2956
A/7000
1200' 011/6 hrs

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

