

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02054-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 19-11S-16W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: POTTER Well #: 1
County: ELLIS Total Vertical Depth: 3330 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3327	0	125 SX CMT
SURF	8.625	1006	0	500 SX CMT

\$ 108.23

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2006 3:30 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CURTIS GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 260 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2006 6:45 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

04/12/2006
TIH with tubing to 3324' - mixed and spotted 20 sxs cement with 100# hulls. POOH. SIFN.
04/13/2006
Shot casing free at 1468'.
Pulled up to 1400' - pumped 100 sxs cement with 300# hulls.
Pulled up to 1050' - spotted 40 sxs cement with 100# hulls.
Pulled up to 550' and circulated cement with 50 sxs.
POOH. Topped with 40 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3325	3329		
3320	3322		

Remarks: ALLIED CEMENTING COMPANY.


Plugged through: CSG

INVOICED

4-24-06
2006061521

District: 04

Signed _____



(TECHNICIAN)

RECEIVED

APR 21 2006

KCC WICHITA

Form CP-2/3

APR 17 2006

PCT

WADICED

J. M. HUBER & FERGUSON #1 POTTER-SCHIMMER A 19-11-16W- SW SW SE
 Contr. CROWE DRILLING CO ELLIS County
 E 1835 Comm. 3-27-48 Comp. 7-30-48 IP 157 BOPD PHY POT

Tops	Depth	Datum	Casing
Anh	1011	+874	
			8" 1006 ACID 1500
			5" 3326 SWB 9 BOPH
LANS	3041	-1206	PERF 6 S. 3320-22
B/KC	3286	-1451	CO: 3330: DE 3337
			SWB 18 BO & 12 BW/7 HRS:
SIMP	3320	-1485	PB 3335
			ACID 1000
ARB	3326	-1491. x ✓	SWB 51 BO & 25 BW/24 HRS
T.D.	3330	-1495	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS