

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20126-00-00
Spot: SENWSE Sec/Twnshp/Rge: 12-5S-22W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: NELSON C Well #: 2
County: NORTON Total Vertical Depth: 3471 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-------------------|
| PROD | 4.5 | 3468 | 0 | w/unknown sxs cmt |
| SURF | 8.625 | 251 | 0 | w/unknown sxs cmt |

112.81

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2006 12:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Revd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered out 200 sxs Swift Multi-Density cement with 500# hulls.
Dakota broke in - dumped sand. Anhy. 1646'.
Rods parted at 2225'. Tubing parted 300'. Fluid level 50'. Dakota broke in.
Unable to recover tubing. Bridge at 2251'. Backed tubing off at 2230'.
Decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2006 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2175'. Swift Services pumped 80 sxs SMD with 200# hulls - circulated cement.
PTOH. Squeezed 4 1/2" with 15 sxs.
Max. P.S.I. 300#. S.I.P. 300#.
Hooked up to backside and pumped 15 sxs SMD.
Max. P.S.I. 450#. S.I.P. 450#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3468 | 3471 | OH | |
| 3335 | 3368 | | |

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

INVOICED
DATE 4-24-06
BY 2006061522

District: 04

HP

Signed Richard Williams
(TECHNICIAN)

RECEIVED

Form CP-2/3

APR 21 2006

KCC WICHITA

APR 13 2006

PKT

WADICEN

R.P. NIXON OPERATIONS
207 W. 12TH ST.

#2 NELSON "C"

12-5-232W
SE NW SE

HAYS, KS.

CONTR ABERCROMBIE DRG., INC. CTRY NORTON

GEOL _____ FIELD DENSMORE

E 2052 KB CM 3/27/78 CARD ISSUED 5/18/78 P 15 BOPD + WTR
REAG 3468-71

| | | | |
|---|---|---|---|
| | | | |
| + | + | + | + |
| + | + | + | + |
| + | + | + | + |

API 15-137-20,126

| SMP | TOPS | DEPTH | DATUM |
|------|------|-------|-------|
| | | | |
| ANH | | 1646 | + 406 |
| HEEB | | 3173 | -1121 |
| TOR | | 3205 | -1153 |
| LANS | | 3221 | -1169 |
| BKC | | 3407 | -1355 |
| REAG | | 3467 | -1415 |
| RTD | | 3470 | -1418 |
| DDTD | | 3471 | -1419 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

8-5/8" 252, 4 1/2" 3468
NO LOG
NO DST'S
MICT - CO TD, DD 3471', SWB 2 BFPH,
90% OIL, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS