

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21518-00-01  
Spot: NWNWSESW Sec/Twnshp/Rge: 16-26S-8E  
1007 feet from S Section Line, 3879 feet from E Section Line  
Lease Name: LARCOM A Well #: 3  
County: BUTLER Total Vertical Depth: 2585 feet

Operator License No.: 6974  
Op Name: THORNTON DRILLING COMPANY PTR  
Address: 1577 P RD  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2584		
SURF	7	105		

# 84.01

Well Type: EOR UIC Docket No: E21366.1 Date/Time to Plug: 04/18/2006 8:30 AM  
Plug Co. License No.: 6974 Plug Co. Name: THORNTON DRILLING COMPANY PTRNSHIP  
Proposal Rcvd. from: DICK THORTON Company: THORNTON DRILLING COMPANY Phone: (620) 583-6273

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/18/2006 12:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH with tubing at 1860'. United Cementing mixed and pumped 15 sacks of class A with 2% CC. Tagged cement at 1760'. RIH with rubber plug at 270' and dumped 4 sacks of 200 lb sand. RIH with tubing at 250'. United Cementing mixed and pumped 28 sacks of 60/40 posmix with 4% gel to surface.

PBTD 1870'  
Perfs 1834-1840  
4-1/2" casing cemented to surface on backside

Perfs:

RECEIVED  
KCC DISTRICT #2  
APR 19 2006  
WICHITA, KS

Remarks:

Plugged through: TBG

INVOICED  
DATE 4-24-06  
2006061525

District: 02

Signed

Duane R. Krueger  
(TECHNICIAN)

RECEIVED  
APR 21 2006  
KCC WICHITA

Form CP-2/3

PCT