

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25476-00-00  
Spot: N2NWSWNE Sec/Twnshp/Rge: 36-13S-20W  
1490 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: PFEIFER Well #: 1-B  
County: ELLIS Total Vertical Depth: 3840 feet

Operator License No.: 3194  
Op Name: TRI UNITED, INC  
Address: 950 270TH AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3838	0	w/unknown sxs cmt
SURF	8.625	220	0	w/unknown sxs cmt

\$ 124.80

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/14/2006 10:00 AM  
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE  
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED, INC. Phone: (785) 628-3670

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/14/2006 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Sanded off bottom to 3750' and topped with 5 sxs cement using a dump bailer.  
Shot casing at 2030' - 1850' and 1550' - 997'.  
Casing shot free at 997'.  
Pulled up to 991' - mixed and pumped 125 sxs cement with 300# hulls.  
Pulled up to 825' - spotted 50 sxs cement with 200# hulls.  
Pulled up to 160' and circulated cement with 50 sxs.  
POOH. Topped with 5 sxs cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

INVOICED  
DATE 4-24-06  
NO. 2006061526

District: 04

Signed

(TECHNICIAN)

100.

APR 17 2006

RECEIVED

APR 21 2006

KCC WICHITA

Form CP-2/3

PCT