

KANSAS CORPORATION COMMISSION  
 OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
 Please TYPE Form and File ONE Copy

Form CP-1  
 September 2003  
 This Form must be Typed  
 Form must be Signed  
 All blanks must be Filled

API # 15 - 015-20853-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date \_\_\_\_\_.

Well Operator: VESS OIL CORPORATION KCC License #: 5030  
(Owner/Company Name)

Address: 8100 E. 22nd Street North, Bldg. 300 City: Wichita  
(Operator's)

State: KS Zip Code: 67226 Contact Phone: (316) 682 - 1537 X103

Lease: Paulson A Well #: 98 Sec. 2 Twp. 26S S. R. 04E  East  West

App. Own: NW - NE - SW Spot Location / QQQQ County: Butler

2445 2179 KCC-SKA-2-2-06-AS Per Scout Card #2.  
 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2540 2674  
 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8 Set at: 231' Cemented with: 150 Sacks

Production Casing Size: 5-1/2 Set at: 2108' Cemented with: 225 Sacks

List (ALL) Perforations and Bridgeplug Sets: Lansing 1652-73'; KC 1960-68'; 1981-88

Elevation: 1380/1385 ( G.L. /  K.B.) T.D.: 2445' PBTD: 2091' Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Run tbg to 1650': 35 sx Class A, 3% cc. Pull up unit, wireline tag plug. Set second plug @ 480'; 15 sx Class A, 3% cc (above casing leaks) top plug: Perf 5-1/2 @ 280'.

Circ. full and back to surface. 60/40 Pozmix, 4% gel

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**RECEIVED**  
**FEB 01 2006**  
**KCC WICHITA**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Casey Coats

Phone: (316) 682 - 1537 X104

Address: 8100 E. 22nd St., North, Bldg. 300 City / State: Wichita, KS 67226

Plugging Contractor: United Cementing and Acid Company, Inc. KCC License #: 30437  
(Company Name)

Address: 2510 W. 6th, El Dorado, KS 67042 Phone: (316) 321- - 4680  
(Contractor's)

Proposed Date and Hour of Plugging (if known?): 1/27/06 - 10:00 a.m. Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/27/06 Authorized Operator / Agent: Casey Coats  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202