

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 051-22,340-00-04 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: Taurus Oil Co KCC License #: 6127
(Owner / Company Name) (Operator's)

Address: P.O. Box 981 City: Hays

State: Kansas Zip Code: 67601 Contact Phone: (785) 628 - 1727

Lease: Wilson Well #: 2-B Sec. 29 Twp. 14 S. R. 19 East West

W2 - E2 - NE Spot Location / QQQQ County: Ellis

3960 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

965 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # 23,736 ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 270 Cemented with: 185 Sacks

Production Casing Size: 5 1/2 Set at: 3825 Cemented with: 580 w/DV Tool Sacks

List (ALL) Perforations and Bridgeplug Sets: 3799-3824

Elevation: 2132 (G.L. / K.B.) T.D.: 3825 P.B.T.D.: _____ Anhydrite Depth: 1410
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): pressure annulus with cement, then mix and pump 50sx cement with 500# hulls, follow with 20sx gel spacer, follow with 150 sx 60/40 posmix/10% gel and pressure casing to 500#

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? not available

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Jeff Koron Phone: (785) 628 - 1727

Address: P.O. Box 981 City / State: Hays, Kansas

Plugging Contractor: Allied Cementing KCC License #: _____
(Company Name) (Contractor's)

Address: P.O. Box 31 Russell, Ks Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1-27-06 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 01 2006

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Koron, Jeff dba Taurus Oil Company
PO Box 981
Hays, KS 67601

February 02, 2006

Re: WILSON B #2
API 15-051-22340-00-01
W2E2NE 29-14S-19W, 3960 FSL 965 FEL
ELLIS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely



David P. Williams
Production Supervisor