

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

RECEIVED

Form CP-1
September 2003

2006 Form must be Typed
Form must be Signed
All blanks must be Filled

KCC WICHITA

API # 15- 15-081-21045 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date S08-14-96 C10-31-96

Well Operator: BP AMERICA PRODUCTION COMPANY KCC License #: 5952

Address: P. O. BOX 3092, WL1, RM 3.201 City: HOUSTON (Operator's)

State: TEXAS Zip Code: 77253-3092 Contact Phone: 281 366-4395

Lease: LEMON B SWD Well #: 2 Sec. 10 Twp. 27S R. 32W East West

SW SW SW SE Spot Location/QQQQ County HASKELL

100 Feet from (in exact footage) North / South (from nearest outside section corner) Line of Section (not Lease Line)

2565 Feet from (in exact footage) East / West (from nearest outside section corner) Line of Section (not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # D27339.0 ENHR Docket # _____ Other _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 4 - 1/2" Set at: 1077' Cemented with: _____ Sacks

Production Casing Size: 2 - 3/8" Set at: 1532' Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: 1437' -1531'

Elevation: 2861' (G.L. K.B.) T.D. 1534' PBDT _____ Anhydrite Depth Glorietta
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): SEE ATTACHED PROCEDURES.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Logs were sent in with ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

DEANN SMYERS Phone: 281 366-4395

Address: P. O. BOX 3092, WL 1, RM 3.201 City/State HOUSTON, TEXAS 77253-3092

Plugging Contractor HALLIBURTON SERVICES KCC License # 5287 99997

Address 210 W Park Ave, Suite 200 OKC, OK 73102 Phone: _____ (Contractor's)

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 04/13/06 Authorized Operator / Agent: DeAnn Smyers
(Signature)

RECEIVED
APR 24 2006
KCC WICHITA

Plugging Procedure

Well Name: Lemon B SWD 2
Location: Section 10 Township 27 Range 32
County: Haskell County
Surface Casing 4.5" surface casing set at 1077'
Sidestring: 2.375" set at 1532'
Injection Interval: Perforations 1437-1531
Pump In Data: Test rate 0.5 bpm @ 380 psi.

NOTE - NOTIFY KCC DISTRICT OFFICE AT LEAST FIVE DAYS IN ADVANCE OF WORK

This procedure was approved via email between Joe Eudey (BP representative) and Steve Durant (KCC representative).

Procedure

1. Pump cement (with cottonseed hulls to plug off the perms) and fill the 2.375" casing from the bottom perms to ground level. Pressure casing to 300 psi.
2. Tie onto annulus between surface casing and 2.375" injection string and fill with cement. Pressure to 300 psi.
3. Cut off and cap casings 5' below ground level.
4. Restore the location.

Cement Information

Class "H" 60/40 poz with 6% gel mixed at 13.2 lb/gal with a yield of 1.53 cu. ft./sk

RECEIVED

APR 24 2006

KCC WICHITA

Plugging Application
Lemon B SWD 2 ("mini" disposal) Abandonment
Sec 10, T27S, R32W
Haskell County, Kansas

The application attached is to abandon the 2.375" fiberglass injection casing in the Lemon B SWD 2. This well was drilled to the Glorietta horizon as a "mini" disposal well and the injection string was cemented back to ground level. BP Amoco is abandoning this well as it has become uneconomic to operate.



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BP America Production Company
2225 West Oklahoma Avenue
Ulysses, KS 67880

April 27, 2006

Re: LEMON B SWD #2
API 15-081-21045-00-00
SWSWSE 10-27S-32W, 100 FSL 2565 FEL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888