

APR 26 2006

CONSERVATION DIVISION  
WICHITA, KS

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 163-23503-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 12-07-05

Well Operator: American Warrior, Inc. KCC License #: 4058

Address: PO Box 399 (Owner / Company Name) City: Garden City (Operator's)

State: KS Zip Code: 67846-0399 Contact Phone: ( 620 ) 275 - 9231

Lease: Dechant-Muir Well #: 1 - 23 Sec. 23 Twp. 8 S. R. 18  East  West

App - SW - NW - NE Spot Location / QQQQ County: Rooks

1125 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2890 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 207 2 11<sup>per</sup> CP<sup>2 1/3</sup> Cemented with: 150 Sacks

Production Casing Size: \_\_\_\_\_ Set at: 1000 ap. Cemented with: \_\_\_\_\_ Sacks

List (ALL) Perforations and Bridgeplug Sets: \_\_\_\_\_

Elevation: 1976/1981 ( G.L. /  K.B.) T.D.: 3500 P.B.T.D.: \_\_\_\_\_ Anhydrite Depth: \_\_\_\_\_ (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill hole with rotary mud to 3450' and spot 25 sx of cement. Fill hole with rotary mud to 1350' and spot 25 sx of cement. Fill hole with rotary mud to 875' and spot 100 sx of cement. Fill hole with rotary mud to 260' and spot 40 sx cement. Fill hole with rotary mud to 40' and spot 10 sx of cement. Put 15 sx in rathole.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Cecil O'Brate

Phone: ( 620 ) 275 - 9231

Address: PO Box 399 City / State: Garden City KS 67846-0399

Plugging Contractor: Berentz Drilling Company, Inc. KCC License #: 5892

Address: PO Box 782228 Wichita KS 67278-2228 (Company Name) Phone: ( 316 ) 685 - 5908 (Contractor's)

Proposed Date and Hour of Plugging (if known?): 12-15-05 at 7:00 a.m.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4-26-06 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202  
well already plugged - Bill-Dig Dist 4