

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED

Form CP-1
September 2003

APR 24 2006

Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

KCC WICHITA

API # 15-15-093-21533-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date S07-19-96 C10-17-96

Well Operator: BP AMERICA PRODUCTION COMPANY KCC License #: 5952

Address: P. O. BOX 3092, WL1, RM 3.201 City: HOUSTON
(Owner/Company Name) (Operator's)

State: TEXAS Zip Code: 77253-3092 Contact Phone: 281 366-4395

Lease: SCHAEFER SWD Well #: 1 Sec. 16 Twp. 23S R. 35W East West

SE NE Spot Location/QQQQ County KEARNY

2645 Feet from (in exact footage) North / South (from nearest outside section corner) Line of Section (not Lease Line)

135 Feet from (in exact footage) East / West (from nearest outside section corner) Line of Section (not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # D 27365.0 ENHR Docket # _____ Other _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 5 - 1/2" Set at: 1031' Cemented with: _____ Sacks

Production Casing Size: 2 - 3/8" Set at: 1647' Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: 1556' -1647'

Elevation: 3027' (G.L. K.B.) T.D. 1650' PBDT _____ Anhydrite Depth Glorietta
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): SEE ATTACHED PROCEDURES.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Logs were sent in with ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

DEANN SMYERS Phone: 281 366-4395

Address: P. O. BOX 3092, WL 1, RM 3.201 City/State HOUSTON, TEXAS 77253-3092

Plugging Contractor HALLIBURTON SERVICES KCC License # 5287 99997
(Company Name) (Contractor's)

Address 210 W. Park Ave Suite 2000, OKC, OK 73107 Phone: _____

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 04/13/06 Authorized Operator / Agent: DeAnn Smyers
(Signature)

RECEIVED
APR 24 2003
KCC WICHITA

Plugging Procedure

Well Name: Schaefer SWD 1
Location: Section 16 Township 23 Range 35
County: Kearny County
Surface Casing 5.5" surface casing set at 1031'
Sidestring: 2.375" set at 1647'
Injection Interval: Perforations 1556-1647
Pump In Data: Test rate 1.5 bpm @ 250 psi.

NOTE - NOTIFY KCC DISTRICT OFFICE AT LEAST FIVE DAYS IN ADVANCE OF WORK

This procedure was approved via email between Joe Eudey (BP representative) and Steve Durant (KCC representative).

Procedure

1. Pump cement (with cottonseed hulls to plug off the perms) and fill the 2.375" casing from the bottom perms to ground level. Pressure casing to 300 psi.
2. Tie onto annulus between surface casing and 2.375" injection string and fill with cement. Pressure to 300 psi.
3. Cut off and cap casings 5' below ground level.
4. Restore the location.

Cement Information

Class "H" 60/40 poz with 6% gel mixed at 13.2 lb/gal with a yield of 1.53 cu. ft./sk

Plugging Application
Schaefer SWD 1 ("mini" disposal) Abandonment
Sec 16, T23S, R35W
Kearny County, Kansas

RECEIVED

APR 24 2006

KCC WICHITA

The application attached is to abandon the 2.375" fiberglass injection casing in the Schaefer SWD 1. This well was drilled to the Glorietta horizon as a "mini" disposal well and the injection string was cemented back to ground level. BP Amoco is abandoning this well as it has become uneconomic to operate.

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BP America Production Company
2225 West Oklahoma Avenue
Ulysses, KS 67880

April 28, 2006

Re: SCHAEFER SWD #1
API 15-093-21533-00-01
SESENE 16-23S-35W, 2645 FSL 135 FEL
KEARNY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor