

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 073 - 204450000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 8/3/69.

Well Operator: BEAR PETROLEUM, INC. KCC License #: 4419
Address: P.O. BOX 438 (Owner / Company Name) City: HAYSVILLE (Operator's)

State: KS Zip Code: 67060 Contact Phone: (316) 524 - 1225

Lease: SCOTT Well #: 95 Sec. 19 Twp. 23 S. R. 9 East West
NE - SE - NE Spot Location / QQQQ County: GREENWOOD

3630 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 44' Cemented with: 35 Sacks

Production Casing Size: 5 1/2 " Set at: 2571' Cemented with: 250 Sacks

List (ALL) Perforations and Bridgeplug Sets: TD 25' OH

Elevation: 1603 (G.L. / K.B.) T.D.: 2645 PBTD: 2596 Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): According to the rules and regulations of the KCC

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dick Schremmer
Bear Petroleum, Inc. Phone: (316) 524 - 1225

Address: P.O. BOX 438 City / State: HAYSVILLE, KS 67060

Plugging Contractor: K.E. Snyder Company, LLC KCC License #: 32147
(Company Name) (Contractor's)

Address: P.O. Box 107, Hamilton, KS 66853-0107 Phone: (620) 678 - 3613

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 3/9/06 Authorized Operator / Agent: _____ (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 10 2006
KCC WICHITA

15073 204450000

REMARKS CONT:

Thirty-two, six inch segments of the core were sealed in crude oil from the lease and sent to the Bureau of Mines, Bartlesville, Oklahoma. The remainder of the core was picked up at the rig by Kansas Cores and analyzed in Wichita, Kansas.

Separate reports will be furnished by Kansas Cores and the Bureau of Mines.

5½ inch casing was cemented at 2571 feet and the hole should be plugged back to around 2600 feet after running the radioactivity log.

FORMATIONS:

Following are the depths of the tops of the formations as determined by sample analysis. All measurements are taken from the Kelly Bushing.

<u>Formation</u>	<u>Depth</u>	<u>Datum</u>
Kansas City	1911	(- 308)
Base Kansas City	2083	(- 480)
Cleveland	2093	(- 490)
Marmaton	2207	(- 604)
Pawnee	2234	(- 631)
Fort Scott	2301	(- 698)
Cherokee	2359	(- 756)
Cattleman	2422	(- 819)
Bartlesville Zone	2535	(- 923)
Bartlesville Sand	2569	(- 966)
Base Sand	2636	(-1033)
Rotary Total Depth	2645	(-1042)

Handwritten calculation: 2535 - 932 = 1603

RESERVOIRS:

Kansas City 1911

2075-2078 Limestone, fair crystalline porosity, spotted light stain.

Cattleman Sand 2422

2422-2430 Sandstone, fine to medium grain, micaceous sub-angular. No staining.

2430-2450 Sandstone, fine to medium grain, micaceous sub-angular, slightly limy.

RECEIVED
MAR 10 2006
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bear Petroleum, Inc.
PO Box 438
Haysville, KS 67060

April 10, 2006

Re: SCOTT #95
API 15-073-20445-00-00
NESENE 19-23S-9E, 3630 FSL 330 FEL
GREENWOOD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300

Sincerely



David P. Williams
Production Supervisor