

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record

K.A.R. 82-8-117

API NUMBER 15-077-21552-00-00
LEASE NAME Schmisser "A"
WELL NUMBER 1-28

RECEIVED
APR 20 2006
KCC WICHITA

TYPE OR PRINT

NOTICE: Fill out completely and return to Cons. Div. office within 30 days. 330 Ft. from North Line of Section
1980 Ft. from West Line of Section

LEASE OPERATOR McCoy Petroleum Corporation Lic # 5003 SPOT LOCATION N/2 NE NW
ADDRESS 8080 E. Central, Suite 300 Section 28 Township 31s Range 8w
CITY, STATE, ZIP Wichita, Kansas 67206 County Harper
PHONE # 316-636-2737 Date Well Completed 04/12/06
Character of Well Dry and Abandoned Date Plugging Commenced 04/12/06
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 04/12/06

The plugging proposal was approved on 04/12/06 (date)
by Dwayne Krueger (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4412

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands		0	32			
Redbeds	Shale	32	214	8-5/8"	211	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged well with heavy mud from 4412' to 1350', then 35 sx at 1350', 35 sx at 900', 35 sx at 272' and 25 sx at 60' to surface. Plugged rathole w/ 15 sx, mousehole w/10 sx. Total cement used = 155 sx of 60/40 Poz with 4% Gel. Plugging completed at 8:30 am on 04/12/06. Allied Cementing ticket # 23713. Received plugging orders from Dwayne Krueger at 5:00 pm on 04/10/06. Sterling Drilling reported to KCC (Virgil Clothier) on 04/12/06.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice- President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 13th day of April, 2006



Pamela S. Fields
(Notary Public)

My Commission Expires: _____

RTT

RECEIVED
 APR 20 2006
 KCC WICHITA

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
 Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Schmisseur "A" 1-28

LOCATION: N/2 NE NW
API: 15-077-21552-00-00

Section 28 T 31s R 8w
 Harper County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 04/03/06
COMPLETED: 04/12/06

TOTAL DEPTH:	DRILLER	4412	FEET
	LOGGER	No Log	FEET

Ground Elevation: 1564
KB Elevation: 1573

LOG

0 -	2 FEET	Top Soil
2 -	18 FEET	Fine Sand
18 -	32 FEET	Sand and Gravel
32 -	1100 FEET	Redbeds
1100 -	1640 FEET	Shales and Salt
1640 -	4412 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud at 5:00 pm on 04/03/06. Drilled 12-1/4" hole to 225'. Ran 5 joints of new 23# 8-5/8" surface casing tallied 211.05' set at 220.05' KB. Cemented with 225 sx 60/40 Poz, 2% Gel, 3% CC, 1/4# Cello. Plug down at 11:00 pm on 04/03/06 by Acid Services. Ticket #12445. Cement did circulate. Strapped bottom 2 joints, of SP, then welded collars on next 3 joints.

Plugging Data:

Plugged well with heavy mud from 4412' to 1350', then 35 sx at 1350', 35 sx at 900', 35 sx at 272' and 25 sx at 60' to surface. Plugged rathole w/ 15 sx, mousehole w/10 sx. Total cement used = 155 sx of 60/40 Poz with 4% Gel. Plugging completed at 8:30 am on 04/12/06. Allied Cementing ticket # 23713. Received plugging orders from Dwayne Krueger at 5:00 pm on 04/10/06. Sterling Drilling reported to KCC (Virgil Clothier) on 04/12/06.

DEVIATION SURVEYS

3/4 degree(s) at	225	feet
1/4 degree(s) at	4269	feet