

RECEIVED

APR 20 2006

Form CP-4
December 2003
Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA

Lease Operator: Woolsey Operating Company, LLC
Address: 125 N. Market, Wichita, KS 67202
Phone: (620) 886-5606 Operator License #: 33168
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 3/21/2006 (Date)
by: DeWayne Krueger (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 4175 Bottom: 4185 T.D. 4238
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 095-21868-00-00 KCC PKT
Lease Name: Bohrer GU 4-20-06 Per
Well Number: 3 C-1 Intent.
Spot Location (QQQQ): 80N100E - S/2 - NW - SW KCC
1730-1763 Feet from North / South Section Line PKT
700-4634 Feet from East / West Section Line 4-20-06
Sec. 34 Twp. 29 S. R. 9 East West Per
County: Kingman GPS'd
Date Well Completed: 5/17/2004 Etgs.
Plugging Commenced: 03/21/2006
Plugging Completed: 03/23/2006

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				13 3/8	88	None
				10 3/4	218	None
				5 1/2	4285	2920

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
3/21 - MIRU, set CIBP at 4125', spot 2 sacks cemet with dump bailer, rig up casing tools. 3/22 - stretch and cut pipe at 2920', pull casing to 1370'. 3/23 - Allied load hole with 15 sacks, 300 hulls, pump 35 sacks 60/40 POZ 4% gel, pull to 920', spot 35 sacks pull to 230', load to surface, pull casing, tie on 10 3/4, pump 20 sacks, top off with 70' sand and 2 sacks quick crete

Name of Plugging Contractor: Clarke Corporation License #: 5105
Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC
State of Kansas County, Barber, ss.
John Swinford

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 18 day of April, 20 06
Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT