

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Midwestern Exploration Co.
Address: 3500 S. Boulevard, Suite 2B
Phone: (405) 340-4300 Operator License #: 5263
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Council Grove Depth to Top: 3206' Bottom: 3210' T.D. _____
Wreford Depth to Top: 3052' Bottom: 3062' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-119-21137-00-00
Lease Name: Shank
Well Number: 1-14
Spot Location (QQQQ): _____ - C - S/2 - NE/4
1980 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 14 Twp. 32 S. R. 30 East West
County: Meade
Date Well Completed: 7-5-05
Plugging Commenced: 10-12-05
Plugging Completed: 10-24-05

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|-------|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Council Grove 3206-10' | water | surface | 1648' | 8 5/8" | 1648' | |
| Wreford 3052-62' | water | GL | 3400' | 4 1/2" | 3400' | 1808' |
| | | | | | | |
| | | | | | | |


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

#1 Set CIBP @ 3005', 10' cement on top, circulate well w/mud, pump, circulate cement from 1600'-1750', circulate cement plug from 450' to 550', top well up w/ 20 sx 40' to 4', cap well and put information on cap.

Name of Plugging Contractor: Eagle Energy Services, Inc. License #: 7407
Address: P. O. Box 1597, Liberal, Kansas 67905
Name of Party Responsible for Plugging Fees: Midwestern Exploration Co.
State of Oklahoma County, Oklahoma, ss.

Dale J. Lollar, President Midwestern Exploration Co. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Dale J. Lollar President
(Address) 3500 S. Boulevard, Suite 2B, Edmond, OK 73013



SUBSCRIBED and SWORN TO before me this 20th day of April, 2006
Virginia Means My Commission Expires: 7/12/2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
APR 24 2006
KCC WICHITA