

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-195-22,324-00-00

LEASE NAME Applegate Unit

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1,470 Ft. from ^N Section Line

120 Ft. from E Section Line

SEC. 12 TWP. 15 RGE. 23 (E) or (W)

COUNTY Trego

Date Well Completed 4-6-06

Plugging Commenced 4-6-06

Plugging Completed 4-6-06

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 W. 12th, Hays, KS 67601

PHONE# (785) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved, on 4-6-06 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,244'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	<u>221-219</u>	Cmtd. w/160 sax
					<u>KCC</u>	<u>4-26-06 PKI</u>
					<u>Per CP213</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Push bridge plug to 1,675', pump 25 sax cement down drill pipe. Push bridge plug to 750'. Pump 100 sax cement down drill pipe. Push bridge plug to 275', pump 40 sax cement down drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of ~~operator~~) or ~~operator~~ Contractor above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.


(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 14th day of April, 2006

Ruth Phillips
Notary Public

My Commission Expires: _____



RECEIVED
APR 19 2006
KCC WICHITA