

RECEIVED

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

APR 21 2006

WELL PLUGGING RECORD

K.A.R. 82-3-117

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: Carmen Schmitt Inc.

Address: PO Box 47, Great Bend, KS 67530

Phone: (620) 793-5100 Operator License #: 6569

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: April 5, 2006 (Date)

by: Roger Moses (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
L/KC Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-01332-00-00

Lease Name: Adams B

Well Number: 1

Spot Location (QQQQ): _____ - C - SE - SW
660 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 33 Twp. 08 S. R. 16 East West

County: Rooks

Date Well Completed: August 21, 1961

Plugging Commenced: April 5, 2006

Plugging Completed: April 5, 2006

KCC
4-25-06
PKT
Per
RBDins

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	183'	8 5/8"	Aug 1961	no
		surface	3375	5 1/2"	Aug 1961	no

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

LK Wireline perfs at 1250 and 850 feet. Ran tubing to 2100' and spot 75 sacks cement with 2 sacks hulls. Pulled tubing to 1200 feet. Circulated cement to surface with 100 sacks cement and 2 sacks hulls. Pulled tubing and finished plugging with 15 sacks cement and 1 sack hulls. Pressured to 600 psi, shut in at 500 psi, holding. Put 50 sacks cement down annulus at 250 psi, shut in with 50 psi on annulus.

Name of Plugging Contractor: DS&W Well Servicing, Inc. License #: 6901


Address: PO Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Carmen Schmitt Inc.

State of Kansas County, Barton, ss.

Jacob Porter (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jacob L. Porter

(Address) PO Box 47, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 20th day of April, 20 06

Elaine Scheck My Commission Expires: 12-13-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT

ALLIED CEMENTING CO., INC.

21214

RECEIVED

APR 21 2006

SERVICE POINT:

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

KCC WICHITA

R

DATE <u>4/5/06</u>	SEC. <u>33</u>	TWP. <u>8s</u>	RANGE <u>16W</u>	CALLED OUT	ON LOCATION <u>9:30 AM</u>	JOB START	JOB FINISH <u>1:00 P.M.</u>
LEASE <u>ADAMS</u>	WELL # <u>B-1</u>	LOCATION <u>NATOMA W to R28</u>		COUNTY <u>Rooks</u>	STATE <u>Ks</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)		<u>N to D.E. 1/2 W N 10</u>					

CONTRACTOR D.S. & W

TYPE OF JOB Plug

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2" DEPTH _____

TUBING SIZE 2" DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED 300 60/40 1000 GEL

500# HULLS

USED 500 SX w/ 5 HULLS

COMMON	<u>144</u>	@	<u>9.60</u>	<u>1382.40</u>
POZMIX	<u>96</u>	@	<u>5.20</u>	<u>499.20</u>
GEL	<u>19</u>	@	<u>15.00</u>	<u>285.00</u>
CHLORIDE		@		
ASC		@		
HULLS	<u>5</u>	@	<u>23.00</u>	<u>115.00</u>
HANDLING	<u>329</u>	@	<u>1.70</u>	<u>559.30</u>
MILEAGE	<u>77/SK/MI</u>			<u>806.05</u>
TOTAL				<u>3646.95</u>

EQUIPMENT

PUMP TRUCK CEMENTER PAUL

409 HELPER SHANE

BULK TRUCK DRIVER JACK

3102

BULK TRUCK DRIVER _____

REMARKS:

Trig @ 2100' SPOT 75 SX w/ 2 HULLS

CIRC CEMENT @ 1200' w/ 1000 SX

and 2 HULLS.

5 1/2" CSG - 15 SX w/ 1 Hull. Press.

to 600# SILENT IN 500#

ANNULUS - 50 SX @ 250# SILENT IN

500#

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE 650.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 35 @ 5.00 175.00

MANIFOLD _____ @ _____

TOTAL 825.00

CHARGE TO: CARMEN SCHMIDT

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Curtis H. Schumacher

PRINTED NAME