

RECEIVED

APR 25 2006

KCC WICHITA

Form CP-4

December 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Lease Operator: Woolsey Operating Company, LLC

Address: 125 N. Market, Wichita, KS 67202

Phone: (620) 886-5606 Operator License #: 33168

Type of Well: Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 03/27/2006 (Date)

by: Gregg Eves (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 4378 Bottom: 4388 T.D. 4920

API Number: 15-007-21404-00-00 Lease Name: Williams Well Number: 1 Spot Location (QQQQ): Feet from 660 635 1980 3425 Section Line North / South East / West Harper County Date Well Completed: 09/18/1989 Plugging Commenced: 03/28/2006 Plugging Completed: 03/30/2006

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

3/28 - set CIBP at 4330', spot 4 sacks cement with dump bailer. 3/29 - rig up casing tools, stretch and cut casing at 3500', pull to 1200' 3/30 - Allied load hole with 10 sacks gel, 300# hulls, spot 35 sacks 60/40 POZ 4% gel at 1200', pull casing to 750' spot 35 sacks, pull to 260', circulate 106 sacks to surface, pull pipe, top off 40' sand and 2 sacks quick crete

Name of Plugging Contractor: Clarke Corporation License #: 5105

Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC


State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above-described well, being first duty

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104



SUBSCRIBED and SWORN TO before me this 21 day of April, 2006

Glenda Morrison My Commission Expires: 11/30/06 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PRT