

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21187-00-01  
Spot: NWNENW Sec/Twnshp/Rgc: 10-34S-6W  
4908 feet from S Section Line, 3783 feet from E Section Line  
Lease Name: MAYO Well #: A 1  
County: HARPER Total Vertical Depth: 4571 feet

Operator License No.: 8061 •  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PARKWAY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4571		
SURF	8.625	276		

\$ 148.56

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/17/2006 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: \_\_\_\_\_  
Perfs 4510' - 20'; PBD 4537' CIBP; sand to 4460' w/ 4 sxs cmt; 35 sxs cmt @ 1100'; 35 sxs cmt @ 700'; circ 300' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/17/2006 10:00 AM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The perforations were covered with sand from 4537' - 4460' and capped with 4 sacks of cement. The 4-1/2" was recovered from 3630' and pulled to 1100' and spotted 35 sacks of cement. Pulled casing to 700' and spotted 35 sacks of cement. Pulled 4-1/2" to 330' and circulated cement to 0'. Pulled 4-1/2" pulled and cement topped off.

60/40 posmix with 4% gel  
Allied #23615

Perfs:

RECEIVED  
KCC DISTRICT #2  
APR 18 2006  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

*[Signature]*  
(TECHNICIAN)

INVOICED  
DATE 4-25-06  
TR. NO. 2006061536

RECEIVED  
APR 25 2006  
KCC WICHITA

PKT