

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00761-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 11-30S-7W  
4915 feet from S Section Line, 5134 feet from E Section Line  
Lease Name: KAUFMAN C Well #: 1  
County: KINGMAN Total Vertical Depth: 4235 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 SOUTH MAIN - SUITE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4234	2160	100 SX
SURF	8.625	214		165 SX

*\$ 137.64*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/22/2006 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Perfs 4164' - 69'; sand back to 4100', cap w/ 4 sxs cmt; rec pipe; 35 sxs cmt @ 1200'; 35 sxs cmt @ 700'; and circ cmt @ 265' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/22/2006 1:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

CIBP set at 4000' and capped with 4 sacks of cement. Casing recovered. Casing pulled to 1200' and spotted 35 sacks of cement. Casing pulled to 700' and spotted 35 sacks of cement. Casing pulled to 265' and cement circulated to surface. Pulled casing from hole and topped off cement.

60/40 posmix with 4% gel  
Allied #23619

Perfs:

Top	Bot	Thru	Comments
4164	4169		

**RECEIVED  
KCC DISTRICT #2  
APR 18 2006  
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

*[Signature]*  
(TECHNICIAN)

**INVOICED**  
DATE 4-25-06  
REF. NO. 2006061537

**RECEIVED**  
APR 25 2006  
KCC WICHITA

*PBT*