

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21795-00-00
Spot: NENWNE Sec/Twnshp/Rge: 35-22S-12W
330 feet from N Section Line, 1650 feet from E Section Line
Lease Name: MCCUNE Well #: A2
County: STAFFORD Total Vertical Depth: 3648 feet

Operator License No.: 32610
Op Name: G T PETROLEUM, INC.
Address: RR 2, BOX 32
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3648	2040	WITH 160 SX CMT
SURF	8.625	278		WITH 200 SX CMT

\$1118 ⁵⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2006 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3330' & 5 SX CMT. PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2006 2:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3330' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 630' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3391	3454		

RECEIVED
FEB 06 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 2-7-06
INV. NO 2006061071

Form CP-2