

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01708-00-02
Spot: SESESW Sec/Twnshp/Rge: 19-19S-5W
343 feet from S Section Line, 2999 feet from E Section Line
Lease Name: HABIGER Well #: 1
County: MCPHERSON Total Vertical Depth: 3436 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3419		
SURF	8.625	170		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2006 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2006 1:30 PM KCC Agent: DAVE WERTZ

Actual Plugging Report:

MIRU. Ran wireline. Bridge at 860'. Ran tubing to 2650' and hit iron. Spotted 35 sacks of cement at 2650' and came out with tubing. Perforated at 900', 500', and 250'. Ran in hole to 900' and spotted 35 sacks of cement. Pull to 500' and spotted 35 sacks of cement. Pulled to 250' and circulated cement to surface.

60/40 posmix with 4% gel

United #6944

Perfs:

**RECEIVED
KCC DISTRICT #2
APR 17 2006
WICHITA, KS**

Remarks: CONTROL #2006-0017-001

Plugged through: TBG

District: 02

Signed

David Wertz
(TECHNICIAN)

RECEIVED Form CP-2/3
APR 21 2006
KCC WICHITA