

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20834-00-00  
Spot: N2N2SE Sec/Twnshp/Rge: 29-17S-40W  
2310 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: ROE Well #: 4  
County: GREELEY Total Vertical Depth: 3035 feet

Operator License No.: 6471  
Op Name: BANKS, R. C.  
Address: 550 W. TEXAS, #935 PO BOX 242  
MIDLAND, TX 79701

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| PROD   | 4.5   | 3034       | 0           | WITH 550 SX CMT |
| SURF   | 8.625 | 265        |             | WITH 175 SX CMT |

98.64

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2006 10:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DAVE OLSON Company: R.C. BANKS Phone: (915) 682-8296

Proposed Plugging Method: PUMP 400# HULLS & 180 SX CMT. FILL TO SURFACE & CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/06/2006 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 400# HULLS & 40 SX CMT. PUMP 185 SX CMT DOWN 4 1/2" TO SURFACE.  
PRESSURED TO 500# & HELD. PUMP 25 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS.  
PRESSURED TO 400# & HELD.

Perfs:


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2988 | 3017 |      |          |
| 2927 | 2956 |      |          |

**INVOICE**  
DATE 4-24-06  
SER. NO. 2006061528  
RECEIVED  
APR 24 2006  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed Ken Jehlik (TECHNICIAN)

Form CP-275

PET