

KCC PCT
4-26-06

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

Per blasting

API Well Number: 15-207-19719-00-00

Spot: NESEW

Sec/Twnshp/Rge: 24-23S-16E

3656 feet from S Section Line, 3159 feet from E Section Line

Lease Name: REMLINGER

Well #: 12

County: WOODSON

Total Vertical Depth: 950 feet

Operator License No.: 30102

Op Name: CHRIESTENSON, ROBERT

Address: PO BOX 41
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD 2		950	0	
SURF 12		40	0	

\$ 35.00

Well Type: EOR

UIC Docket No:

Date/Time to Plug: 04/04/2006 10:00 AM

Plug Co. License No.: 30102

Plug Co. Name: CHRIESTENSON, ROBERT

Proposal Revd. from: ROBERT CHRIESTENSON

Company: CHRIESTENSON, ROBERT

Phone: (620) 963-2342

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO FILL THE 2" CASING WITH CEMENT AND TO FILL THE 2" AND 12' ANNULUS WITH CEMENT FROM 700' TO AT LEAST 650' AND TO CIRCULATE THE ANNULUS FULL OF CEMENT FROM 230' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/04/2006 12:30 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN INTO THE 2" CASING TO 900'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 12" ANNULUS TO 700'. 15 SACKS OF CEMENT WERE PUMPED INTO THE 1" PIPE AT 700'. THE 1" PIPE WAS PULLED TO 230'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AND 12" ANNULUS AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 144 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

APR 19 2006 CPT

CHANUTE, KS

INVOICED

DATE 4-26-06
2006061543

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED

APR 26 2006

KCC WICHITA

PCT