

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21498-00-00
Spot: NESWSW Sec/Twnshp/Rge: 32-32S-5W
990 feet from S Section Line, 990 feet from W Section Line
Lease Name: COADY Well #: 1
County: HARPER Total Vertical Depth: 3802 feet

Operator License No.: 5044
Op Name: WHITE PINE PETROLEUM CORPORATI
Address: 110 S. MAIN ST., SUITE 500
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3802		100 SX CMT
SURF	8.625	304		200 SX CMT

\$ 123.57

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2006 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Perfs 3475' - 98'; PBTD 3710'; sand to 3425' w/ 5 sxs cmt; 35 sxs cmt @ 1050'; 35 sxs cmt @ 650'; and circ 350' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 03/15/2006 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand from 3710' - 3475' and capped with 5 sacks of cement. The casing was recovered from 3220'. Casing pulled to 1050' and spotted 35 sacks of cement. Casing pulled to 650' and spotted 35 sacks of cement. Casing pulled to 350' and cement circulated to 0'.

60/40 posmix with 4% gel

Allied #22924

Perfs:

Top	Bot	Thru	Comments
3475	3498		


**RECEIVED
KCC DISTRICT #2
APR 18 2006
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

INVOICED
DATE 4-25-06
2006061539

RECEIVED
APR 25 2006
KCC WICHITA

PKT