

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21868-00-00
Spot: S2NWSW Sec/Twnshp/Rge: 34-29S-9W
1763 feet from S Section Line, 4634 feet from E Section Line
Lease Name: BOHRER GU Well #: 3
County: KINGMAN Total Vertical Depth: 4291 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	88		175 SX CMT
PROD	5.5	4285		125 SX CMT
SURF	10.75	218		185 SX CMT

\$ 139.46

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2006 1:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: PBTD 4238'; perfs 4175' - 85'; CIBP @ 4125' w/ 2 sxs cmt; rec csg; 35 sxs cmt @ 1400'; 35 sxs cmt circ 250' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/23/2006 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

CIBP set at 4125' and capped with 2 sacks of cement. Casing recovered from 2950'. Casing pulled to 1408' and spotted 35 sacks of cement. Casing pulled to 937' and spotted 35 sacks of cement. Casing pulled to 254' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #23620

Perfs:


Top	Bot	Thru	Comments
4175	4185		

RECEIVED
KCC DISTRICT #2
APR 18 2006
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

INVOICED
DATE 4-25-06
2006061540

RECEIVED
APR 25 2006
KCC WICHITA

Form CP-2/3

PKT