

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03358-00-01
Spot: S2NENE Sec/Twnshp/Rge: 19-15S-13W
4290 feet from S Section Line, 660 feet from E Section Line
Lease Name: GALE SELLENS Well #: 6
County: RUSSELL Total Vertical Depth: 3251 feet

Operator License No.: 5147
Op Name: BEREDCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		2754		
PROD	5.5	3234	0	w/175 sxs cmt
SURF	10.75	432	0	w/216 sxs cmt

\$ 105.006

Well Type: EOR UIC Docket No: E13550.3 Date/Time to Plug: 03/30/2006 11:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DENNIS KIRMER Company: COMPANY TOOLS Phone: (785) 628-6101

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: PARTIAL
Date/Time Plugging Completed: 03/30/2006 3:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Shot tubing off at 1500' - pulled tubing to 1438' and circulated with 140 sxs cement.
Pulled all tubing - squeezed 10 3/4" w/85 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.
Squeezed 5 1/2" casing with 110 sxs cement and 400# hulls.
Max. P.S.I. 300#. S.I.P. 200#.

INVOICED
4-26-06
2006061541

Remarks: ALLIED CEMENTING COMPANY. SCHNEIDER TANK-WATER.

Plugged through: TBG

District: 04

TD

Signed

Roger L Moses
(TECHNICIAN)

APR 21 2006

RECEIVED
APR 26 2006
KCC WICHITA

Form CP-2/3

PKT

CORALENA OIL CO

#6 G. SELLENS

19-15-13W
CSL NE NE

Contr. _____ RUSSELL _____ County

E 1795 Comm 12-4-42 Comp. 12-18-43 IP ~~2 1/2~~

Tops	Depth	Datum
ANHY	778	
TOP	2685	
DODGE	2926	
LAN S	2978	
ARB	3234	
TD	3251	

Casing
10" 432
5" 3234

INDEXED

1400' OIH/75 min

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

+	+	+
+	+	+
+	+	+