

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20970-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 7-3S-26W  
2310 feet from S Section Line, 330 feet from W Section Line  
Lease Name: KNUTSON B Well #: 1-7  
County: DECATUR Total Vertical Depth: 3840 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF   | 8.625 | 261        |             |         |

\$1124.80

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2006 12:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: KEITH VANPELT Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES Witness Type: NONE  
Date/Time Plugging Completed: 04/20/2006 4:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

No ar buckle.  
1st. Plug at 2215' w/25 sxs.  
2nd. Plug at 1490' w/100 sxs.  
3rd. Plug at 311' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

INVOICED  
DATE 4-26-06  
2006061552

District: 04

100

Signed Roger L Moses  
(TECHNICIAN)

APR 21 2006

RECEIVED  
APR 26 2006  
KCC WICHITA

Form CP-2/3

PET