

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21225-00-00
Spot: NWSESW Sec/Twnshp/Rge: 10-16S-11W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: REDETZKE Well #: 1
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1670 BROADWAY #3300
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3360	0	w/75 sxs cmt
SURF	8.625	382	0	w/200 sxs cmt

SI 109.53

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2006 12:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEVIN WILSON Company: LARSON OPERATING ENERGY, IN Phone: (620) 617-6880

Proposed Plugging Method: Emergency plug with rig over the hole.
Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 17 sxs gel.
Well was cut off in slips with disc placed over the well bore and buried.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2006 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech shot a two hole perf at 1250' and 736'.
Express Well Service RIH with tubing to 3000'.
Allied rigged to tubing and pumped 15 sxs gel, followed with 50 sxs 60/40 pozmix with 300# hulls mixed in and displaced to bottom of hole.
Pulled tubing to 1300'. Allied rigged to tubing and pumped 100 sxs cement with 200# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 8 5/8" casing and pumped 15 sxs cement with Max. P.S.I. 100#.
Blew packing out of top of head. No shut in pressure.
Filled 5 1/2" casing to surface with 15 sxs.
Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3360	3370		

Remarks: ALLIED CEMENTING COMPANY-TICKET #18488.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

APR 26 2006

KCC WICHITA

Form CP-2/3

APR 24 2006

PAT

10-16-11W

BRADEN-DEEM, INC.
200 E. 1ST

WICHITA, KS.
CONTR H-30 DRLG., INC.

#1 REDETZKE

10-16-11W
NW SE SW

CTY BARTON

GEOL

FIELD DAVIDSON SE CONF

E 1890 KB CM 9/10/77 CARD ISSUED 3/23/78 IP

P EST 10 BOPD + WTR
ARB 3360-70

+	+	+
+	+	+
+	+	+

API 15-009-21,225

SMP	TOPS	DEPTH	DATUM
ANH	722		+1168
B ANH	750		+1140
EMP	2446		- 556
HOW	2586		- 696
TOP	2622		- 732
HEEB	2918		-1028
LANS	3031		-1141
CONG	3322		-1432
ARB	3349		-1459
RTD	3370		-1480

8-5/8" 382/200sx, 5 1/2" 3360/75sx
NO LOG
DST (1) 3158-85/30-45-30-45, 20' SOCM
SIP 71-121#, FP 60-60#, 60-91#
DST (2) 3194-3225/30-45-30-45, 15' M,
SIP 906-876#, FP 91-81#, 91-91#
DST (3) 3318-55/30-45-30-45, 20' SOCM
SIP 926-856#, FP 91-81#, 91-91#
DST (4) 3354-62/30-45-30-45, TOOL
PLUGGED
DST (5) 3317-70/45-45-45-45, 795'
HOCM, (50-70% OIL) SIP 1085-1085#
FP 132-223#, 325-376#
MICT - CO TD, AC 100, REC LD, SWB AVG
7.59 BFPH + 18% OIL, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS