

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21260-00-02
Spot: N2SESWNW Sec/Twnshp/Rge: 10-16S-11W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: REDETZKE Well #: B1
County: BARTON Total Vertical Depth: 862 feet

Operator License No.: 3882 •
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1670 BROADWAY #3300
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	862	0	w/unknown sxs cmt
SURF	8.625	257	0	w/150 sxs cmt

\$ 35.00

Well Type: SWD UIC Docket No: D21880.0 Date/Time to Plug: 04/21/2006 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEVIN WILSON Company: LARSON OPERATING ENERGY, IN Phone: (620) 617-6880

Proposed Plugging Method: Emergency plug with rig over the hole.
Ordered 50 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2006 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing - stacked out at 230' - pulled to 190'.
Allied rigged to tubing and pumped 20 sxs 60/40 pozmix to circulate cement to surface.
Pulled tubing - tied onto 4 1/2" casing and pumped 5 sxs cement.
Max. P.S.I. 300#. S.I.P. 250#.
Rigged to 8 5/8" and pressured with cement to Max. P.S.I. 1300#. S.I.P. 1300#.

Perfs:


Remarks: ALLIED CEMENTING COMPANY-TICKET #18487.

Plugged through: TBG

INVOICE
DATE 4-26-06
TEL. NO. 2006061546

District: 04

Signed


(TECHNICIAN)

RECEIVED

APR 26 2006

KCC WICHITA

Form CP-2/3

APR 24 2006



JAYHAWK OIL CO. 10-16-11W
 625 SUTTON PLACE #1 REDETZKE 150'N, SE SW NW
 WICHITA, KS.
 CONTR BIG SPRINGS DRIG., INC. CTY. BARTON

GEOL GERALD BECKER FIELD DAVIDSON SE CONF

E 1891 KB CM 11/14/77 CARD ISSUED 12/8/77 IP D&A/ARB
 11/22/77

+	+	+
+	+	+
+	+	+

API 15-009-21,260

SMP	TOPS	DEPTH	DATUM
QH S-	2827	-936	
HEEB	2914	-1023	
TOR	2934	-1043	
DOUG	2945	-1054	
BR LM	3007	-1116	
LANS	3024	-1133	
BKC	3263	-1372	
CONG SD	3322	-1431	
ARB	3331	-1440	
RTD	3350	-1459	

8-5/8" 257/150SX
 NO LOG
 DST (1) 3184-3200/30-45-45-45, 120' GIP
 60' HOCM, 60' OCM, 60' OCMW, SIP 1000-989#, FP 51-81#
 DST (2) 3296-3340/MIS-RUN
 DST (3) 3297-3340/30-45-45-45, 280' MW
 W/OIL SPOTS, SIP 754-653#, FP 102-142#
 DST (4) 3340-50/30-45-90-45, 3' o, 170' MW, SIP 1071-1050#, FP 51-91#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

DRIFTWOOD OIL CO. 10-16-11W
 BOX 123 #1 REDETZKE 'OWWO' 150'N,
 RUSSELL, KS 67665 SE SW NW
 CONTR SMOKY HILL WELL SRV CTY. BARTON

GEOL _____ FIELD DAVIDSON S E

E 1891 KB CM 4/14/79 CARD ISSUED 7/21/79 IP P 7 BOPD, TR W
 LKC 3198 $\frac{1}{2}$ -99
 ARB 3334-52 OA

+	+	+
+	+	+
+	+	+

API 15-009-21,260-A

SMP	TOPS	DEPTH	DATUM
QH SH	2827	-936	
HEEB	2914	-1023	
TOR	2934	-1043	
DOUG	2945	-1054	
BR LM	3007	-1116	
LANS	3024	-1133	
BKC	3263	-1372	
CONG SD	3322	-1431	
ARB	3331	-1440	
RTD	3350	-1459	
ODTD	3373	-1482	

OLD INFO: OPERATOR WAS JAYHAWK OIL CO
 #1 REDETZKE, SPD 11/14/77, SET 8-5/8"
 257/150SX COMPLETED AS D&A/ARB
 NO LOG
 DST (1) 3184-3200/30-45-45-45, 120' GIP
 60' HOCM, 60' OCM, 60' OCMW, SIP 1000-989#, FP 51-81#
 DST (2) 3296-3340/MIS-RUN
 DST (3) 3297-3340/30-45-45-45, 280' MW
 W/OIL SPOTS, SIP 754-653#, FP 102-142#
 DST (4) 3340-50/30-45-90-45, 3' o, 170' MW, SIP 1071-1050#, FP 51-91#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

NEW INFO: RE-ENTERED 4/14/79, WSH DWN
 DD 3373 TD, SET 4 $\frac{1}{2}$ " 3372
 (OVER)

DRIFTWOOD OIL CO. #1 REDETZKE "OWWO" 10-16-11W
 150'N,
 SE SW NW

MICT - CO, PF (ARB) 3351-52, 3334-38, PF (KC) 3198 $\frac{1}{2}$ -99, AC 250,
 POP