

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00735-00-01
Spot: NENWSE Sec/Twnshp/Rge: 32-9S-18W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: RICHARDSON OWWO Well #: 1
County: ROOKS Total Vertical Depth: 3722 feet

Operator License No.: 8133
Op Name: HAMMERSCHMIDT, WILLIAM E
Address: 904 S SECTION LINE
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3718	0	w/150 sxs cmt
SURF	8.625	197	0	w/unknown sxs cmt

31 120.97

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2006 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: BILL HAMMERSCHMIDT Company: HAMMERSCHMIDT, WILLIAM E. Phone: (785) 434-2403

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2006 12:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 850' - 1550' - 2050'.
TIH with tubing to 2200' - mixed and spotted 180 sxs cement with 400# hulls.
Pulled up to 900' - circulated cement with 100 sxs and 100# hulls.
POOH. Topped with 20 sxs cement.
Hooked up to the annulus and pumped 50 sxs cement.
Max. P.S.I. 150#. S.I.P. 150#.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

INVOICED
DATE 4-26-06
2006061547

District: 04

Handwritten mark

Signed _____

Handwritten signature of Jay Pfeifer

(TECHNICIAN)

RECEIVED

APR 26 2006

KCC WICHITA

Form CP-2/3

APR 20 2006

Handwritten mark

11-1
 32-9-18W
 NE NW SE
 RICHARDSON
 #1
 GRANT OIL

GRANT OIL #1 RICHARDSON 32-9-18W NE NW SE
 Contr. _____ ROOKS _____ County
 E. 2165^{RB} Comm. _____ Comp. _____ IP 160 BOPD
 .14% WTR

Tops	Depth	Datum
ANH	1520	645
TOP	3120	-955
HEEB	3335	-1170
TOR	3360	-1195
LANS	3378	-1213
ARB		
ARB	3675	-1510
TD	3722	-1557

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

Casing 8" 197 O W W O
 COMP 11-30-56 D & A
 BY OSAGE OIL & GAS
 DST 3382-3404/1 1/2 HR, 480' MDY W, BHP 1185#
 DST 3402-30/1 HR, 60' MDY W, BHP 1320#
 DST 3640-83/1 HR, 12' M, BHP 395#
 DST 3716-22/1 HR, 3500' SW, BHP 1085#

WILLIAMS NO

+	+	+
+	+	+
+	+	+

NEW INFO:
 5" 3718: CO TD
 PERF 12/3690-93
 SH OIL: ACID 1000
 SWB 2 BOPH