

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-00948-00-00  
Spot: SESESW Sec/Twnshp/Rge: 32-9S-18W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: STUCKY Well #: 1  
County: ROOKS Total Vertical Depth: 3728 feet

Operator License No.: 8133  
Op Name: HAMMERSCHMIDT, WILLIAM E  
Address: 904 S SECTION LINE  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3727	0	w/450 sxs cmt
SURF	8.625	196	0	w/150 sxs cmt

\$ 121.16

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2006 12:30 PM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE  
Proposal Rcvd. from: BILL HAMMERSCHMIDT Company: HAMMERSCHMIDT, WILLIAM E. Phone: (785) 434-2403

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
WLTD 3539'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/18/2006 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Annulus full of cement - instant pressure.  
Swaged onto 5 1/2" - mixed and pumped 300 sxs cement with 500# hulls.  
Max. P.S.I. 750#. S.I.P. 250#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

INVOICED  
DATE 4-26-06  
TRK. NO. 2006061547

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*

(TECHNICIAN)

RECEIVED

APR 26 2006

KCC WICHITA

Form CP-2/3

APR 20 2006

PET

32-9-18w  
 SE SE SW

OSAGE OIL & GAS

#1 STUCKY

32-9-18w  
SE SE SW

Contr. SIERRA PET

ROOKS

County

E. 2178RB Comm. 8-10-56 Comp. 11-23-56 IP 95 BOPD

Tops	Depth	Datum
ANH	1570	608
TOP	3138	-960
HEEB	3350	-1172
TOR	3376	-1198
LANS	3394	-1216
B/KC	3610	-1432
CONG	3628	-1450
SIMP	3703	-1525
ARB	3726	-1548
TD	3728	-1550

Casing  
 8" 196 w/ 150#  
 5" 3727 w/ 150#  
 DST 3390-3418/1/2 HR, 8' M, BHP 240#  
 DST 3528-45/45", 40' M, SL OC, BHP 1080#  
 DST 3506-90/90", 135' V H OCM, BHP 1020#  
 DST 3590-3613/1/2 HR, 5' M, SPKS O, BHP 60#  
 DST 3672-91/90", 5' M, BHP 740#  
 DST 3710-28/90", 667' O, BHP 1080#  
 CO 3728: NS: PERF 24/3714-17: 2 1/2-3 BOPD  
 SWB 4 BOPD/5 HRS, TR WTR

WMS NO

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS