

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-085-20059-00-00
Spot: SWSW Sec/Twnshp/Rge: 20-6S-16E
709 feet from S Section Line, 4850 feet from E Section Line
Lease Name: JENKINS Well #: 14-20
County: JACKSON Total Vertical Depth: 2220 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2213		422 SX CMT
SURF	8.625	217		140 SX CMT

\$1 72.15

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/03/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2171' TO 2091', CNT FROM 2091' TO 1574', GEL FROM 1574' TO 250'. CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

TAGGED BOTTOM AT 2187'. PULLED TUBING TO 2183' AND PUMPED 8 SACKS OF GEL AND 70 SACKS OF CEMENT WITH 1 SACK OF COTTON SEED HULLS. HAD CEMENT FROM 2183' TO 1574' AND GEL FROM 1574' TO 250'. PULLED TUBING TO 250' AND CIRCULATED 30 SACKS OF CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2038	2041		
2029	2032		
2010	2012		
1985	1988		
1970	1974		
1955	1957		
1948	1951		
1938	1940		
1902	1904		
1855	1857		
1732	1735		
1624	1626		

RECEIVED
KCC DISTRICT #3
APR 18 2006 TCH
CHANUTE, KS

INVOICED
DATE 4-26-06
2006061548

Remarks:
Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

RECEIVED
APR 26 2006
KCC WICHITA

PET