

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-131-20180-00-00  
Spot: SENWSESE Sec/Twnshp/Rge: 12-3S-14E  
795 feet from S Section Line, 772 feet from E Section Line  
Lease Name: GEORG Well #: 16-12  
County: NEMAHA Total Vertical Depth: 2760 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2754		200 SX CMT
SURF	8.625	268		150 SX CMT

\$ 89.70

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/10/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2709' TO 2535' CEMENT FROM 2535' TO 2301' GEL FROM 2301' TO 300' CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/12/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

TAGGED BOTTOM AT 2587'. PULLED TUBING TO 2556' AND PUMPED 35 SACKS OF CEMENT AND 14 SACKS OF GEL WITH 1 SACK OF COTTON SEED HULLS. HAD CEMENT FROM 2556' TO 2250' AND GEL FROM 2250' TO 300'. CIRCULATED 40 SACKS OF CEMENT FROM 300' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2483	2485		
2452	2453		
2422	2426		
2404	2406		
2394	2396		
2351	2353		

RECEIVED  
KCC DISTRICT #3  
APR 18 2006 TCH  
CHANUTE, KS

INVOICED

Remarks:

Plugged through: TBG

DATE 4-26-06  
VV. NO. 2006061548

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

RECEIVED  
APR 26 2006  
KCC WICHITA

PKT