

KANSAS

Form CP-3
Rev. 6-4-68

Y STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1973
CONSERVATION DIVISION
Wichita, Kansas
5-4-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20600-0000

Operator's Full Name Derrick-American Oil, Incorporated,
Complete Address 305 Petroleum Building, Wichita, Kansas.
Lease Name Super Well No. 1
Location SE-NE-SW Sec. 20 Twp. 7 Rge. (E) (W) 24
County Graham Total Depth 2770'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Gabbert-Jones, Incorporated,
Address 830 Sutton Place, Wichita, Kansas. License No.
Operation Completed: Hour 11:45 AM Day 1 Month 5 Year 1973

The above well was plugged as follows:

295'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement
thru DP from 1275' to 950'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 5/4/73
INV. NO. 7321-W