

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20401-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1970
CONSERVATION DIVISION
Wichita, Kansas
12-29-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company,

Complete Address 217 North Water, Wichita, Kansas.

Lease Name F. S. Hale Well No. L-V

Location 50' So. of NE-SE-NE Sec. 10 Twp. 7 Rge. (E) (W) 23

County Graham Total Depth 3840'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company,

Address Box #261, Great Bend, Kansas. License No.

Operation Completed: Hour 10:30 PM Day 21 Month 12 Year 1970

The above well was plugged as follows:

358'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud then

Pulled DP to 1250' and displaced 100 Sx. cement thru DP from 1250' to 925'. Pulled

DP to 365' and displaced 25 Sx. cement thru DP from 365' to 290'. Pulled DP, set

bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dehler
Well Plugging Supervisor

INVOICED

DATE 12/31/70

INV. NO. 3135-4