

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 003-24210-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date November 11, 2002.

Well Operator: Meritage KCM Exploration, LLC KCC License #: 33138

Address: 1050 17th Street Suite 975 City: Denver
(Owner / Company Name) (Operator's)

State: Colorado Zip Code: 80265 Contact Phone: (303) 534 - 9513

Lease: Kincaid Well #: 1-10-22-21 Sec. 10 Twp. 22 S. R. 21 East West

NE - SE - SW Spot Location / QQQQ County: Anderson

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2260 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 24' Cemented with: 4 Sacks

Production Casing Size: 5 1/2" 15.5# Set at: 980' Cemented with: 170 Sacks

List (ALL) Perforations and Bridgeplug Sets: None

Elevation: 1029' (G.L. / K.B.) T.D.: 986' PBTD: 980' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Circulate 60/40 Class A/Pozimix cement with 0.5 sacks
cotton seed hulls from PBTD to 4' below ground level; cut casing and weld steel plate 4' below ground level; grade
surface level.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Larry Bryant Phone: (970) 301 - 1411

Address: 115 North Oak City / State: Garnett, Kansas

Plugging Contractor: Consolidated Oil Well Services, Inc. KCC License #: 31440
(Company Name) (Contractor's)

Address: 1322 South Grant Chanute, Kansas 66720 Phone: (620) 431 - 9210

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/28/06 Authorized Operator / Agent: Larry Bryant
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 01 2006
KCC WICHITA



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Meritage KCM Exploration, LLC
Independence Plaza
1050 17th Street - Suite 975
Denver, CO 80265

May 03, 2006

Re: KINCAID #1-10-22-21
API 15-003-24210-00-00
NWNWSE 10-22S-21E, 2310 FSL 2260 FEL
ANDERSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300

Sincerely



David P. Williams
Production Supervisor