

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: SAMUEL GARY JR & ASSOCIATES, INC (ORIG. OPER. WAS BRADEN-DEEM WHO DID NOT P&A WELL IN 1984)
Address: 1670 BROADWAY, SUITE 3300 DENVER, CO 80202
Phone: (303) 831-4673 Operator License #: 3882
Type of Well: OIL (LAST PRODUCED IN 1984) Docket #: _____
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: K C C, Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
ARBUCKLE Depth to Top: 3360 Bottom: 3370 T.D. 3370
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-21225-00-00
Lease Name: REDETZKE
Well Number: 1
Spot Location (QQQQ): _____ - NW - SE SW
990 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 10 Twp. 16 S. R. 11 East West
County: BARTON
Date Well Completed: 1/31/1978
Plugging Commenced: 4/21/2006
Plugging Completed: 4/21/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
ARBUCKLE	OIL & WATER	SURF	382'	8-5/8"	UNKNOWN	NONE
		PROD	3360'	5-1/2"	UNKNOWN	NONE

RECEIVED
MAY 01 2006
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same, depth placed from (bottom), to (top) for each plug set.


CEMENT PLUGS SET THROUGH 2-3/8" TUBING (180 SX 60/40 POZ WITH 10% GEL)
PERFORATED 5-1/2" PROD. CSG (2 JSPF) @ 1250' & 736'. PLACED 15 SX OF GEL SLURRY FOLLOWED BY 50 SX WITH 300# HULLS @ 3000'. Placed 100 SX WITH 200# HULLS @ 1300'. SQUEEZED 15 SX IN ANNULUS BETWEEN 8-5/8" & 5-1/2" CSG TO 100#. PLACED 15 SX TO THE SURFACE IN THE 5-1/2" CSG.

Name of Plugging Contractor: EXPRESS WELL SERVICE License #: 6426
Address: P O BOX 19, VICTORIA, KS 67671
Name of Party Responsible for Plugging Fees: SAMUEL GARY JR. & ASSOCIATES, INC.
State of COLORADO County, DENVER, ss.

THOMAS G. FERTAL (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Thomas G Fertal
(Address) 1670 BROADWAY, SUITE 3300, DENVER, CO 80202

SUBSCRIBED and SWORN TO before me this 26 TH day of APRIL, 2006
Tammy McFadden My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PCT