

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED

APR 28 2006

Form CP-4  
December 2003

KCC WICHITA  
Form must be Signed  
All blanks must be Filled

15-015-19557-0000

Lease Operator: VESS OIL CORPORATION

Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

Phone: (316) 682-1537 Operator License #: 5030

Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: April 26, 2006 (Date)

by: Doug Lewis (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

<u>Viola</u>	Depth to Top: <u>2411</u>	Bottom: <u>2426</u>	T.D. <u>2526</u>
<u>Simpson</u>	Depth to Top: <u>2454</u>	Bottom: <u>2504</u>	T.D. <u>2526</u>
<u>Arbuckle</u>	Depth to Top: <u>2521</u>	Bottom: <u>2526</u>	T.D. <u>2526</u>

API Number: ~~15-015-97,245-00-00~~

Lease Name: Wilson A

Well Number: 260

Spot Location (QQQQ): 80°N - 70°E - C - SW

1400' Feet from  North /  South Section Line

1390' Feet from  East /  West Section Line

Sec. 9 Twp. 25S S. R. 05E  East  West

County: Butler

Date Well Completed: 2/15/54

Plugging Commenced: 4/26/06

Plugging Completed: 4/27/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	sw	2521	2526	10-3/4	87'	none
Simpson	oil & sw	2454	2504	7 (6-5/8)	2521'	none
Viola	sli oil & sw	2411	2426			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2-7/8 tbg stuck inside of 7" csg. Perf holes in tbg & csg @ 2125'. United pumped 50 sx Class A, 3% cc. Wireline tag in tbg @ 2095'. Perf tbg & csg @ 260'.

Circ. up 2-7/8"/7". Mix and pump 50 sx 60/40 Pozmix, 6% gel, cement to surface. Shut 7" valve, mix and pump 175 sx more, no circ.

but lift pressure to 500#. SI. United Ticket 6959 4/27/06: Pmp 100 sx down 10-3/4 & 7 annulus. Holding pressure, cmt is 30' down in 2-7/8 tbg.

1" & fill it back up. Re-pump in 10-3/4 = 100 sx. Holding pressure. United Ticket #6960. Done 10:00 a.m. - KCC witness, Duane Krueger

Name of Plugging Contractor: United Cementing and Acid Company, Inc. License #: 30437

Address: 2560 W. 6th, El Dorado, KS 67042

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Sedgwick, ss.

Casey Coats (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Casey Coats

(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 27th day of April, 2006

Michelle D. Henning  
MICHELLE D. HENNING  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 7/12/09

My Commission Expires: \_\_\_\_\_  
MICHELLE D. HENNING  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 7/12/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*PKG*