

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20205-00-00
Spot: N2S2SW Sec/Twnshp/Rge: 8-35S-28W
1250 feet from S Section Line, 1320 feet from W Section Line
Lease Name: BARRAGREE Well #: 1-8
County: MEADE Total Vertical Depth: 6600 feet

Operator License No.: 30151
Op Name: EASON DRILLING & SERVICES CO.
Address: TWO WEST SECOND STREET
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2920		WITH 2 SX CMT
CIBP		3140		
CIBP		5598		
PKR		5860		
PROD	5.5	6318	2340	WITH 200 SX CMT
SURF	8.625	1513		WITH 800 SX CMT

\$1 214.50

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/20/2006 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 2920' WITH 2 SX CMT. PLUG AT 1540' WITH 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2006 4:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 2920' WITH 2 SX CMT. 1ST PLUG PUMP MUD SPACER AND 50 SX CMT AT 1540'. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. GOOD CIRCULATION ON ALL PLUGS.

Perfs:

Top	Bot	Thru	Comments
6156	6161		
5882	5892		
5806	5834		
3188	3194		
3146	3152		
2972	2980		

RECEIVED
APR 27 2006
KCC WICHITA
INVOICED

Remarks: USED COMMON CEMENT BY SARGENT & LILLAARD.

Plugged through: CSG

DATE 4-27-06
NO. 2006061560

District: 01

RECEIVED
APR 21 2006
KCC Dodge City

Signed

Jerry W. Stapleton PART #
(TECHNICIAN)