

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20332-00-00  
Spot: NWNW Sec/Twnshp/Rge: 6-14S-9W  
4682 feet from S Section Line, 4756 feet from E Section Line  
Lease Name: ZAJIC E Well #: 1  
County: ELLSWORTH Total Vertical Depth: 1402 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1400		
SURF	8.625	215		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/19/2006 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: 35 sxs cmt to plug btm; perf @ 1200', 900' & 265'; 35 sxs @ 1200'; 35 sxs @ 900'; and circ to surf from 265' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/19/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Ran tubing to 1280' and pumped 35 sacks of cement. Pulled tubing and perforated pipe at 1200', 900', and 265'. Ran tubing and pumped 35 sacks of cement at 1200' and 900'. Pumped 65 sacks of cement to circulate from 265' to surface. 21 sacks of cement was circulated on backside through braden head. 7 sacks of cement was pumped to top off well.

60/40 posmix with 4% gel

United Cement #6950

Perfs: **RECEIVED  
KCC DISTRICT #2  
APR 25 2006  
WICHITA, KS**

Remarks: CONTROL #2006-0018-001

Plugged through: TBG

**RECEIVED  
MAY 01 2006  
KCC WICHITA**

District: 02

Signed Meg Eves  
(TECHNICIAN)