

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21718-00-01  
Spot: NWNWSE Sec/Twnshp/Rge: 19-18S-10W  
2346 feet from S Section Line, 2405 feet from E Section Line  
Lease Name: ZINK Well #: 1  
County: RICE Total Vertical Depth: 3310 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3309		
SURF	8.625	257		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2006 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed  
Plugging  
Method:

Sand to 3230'; cap w/ 4 sxs cmt; perf @ 1250', 900' & 310'; 35 sxs @ 1250'; 35 sxs @ 900'; and circ to surf from 310'.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/21/2006 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 3230' and capped with 4 sacks of cement. Perforated at 1250', 900', and 310'. Ran tubing and pumped 35 sacks of cement at 1250', 900', and 130 sacks of cement at 310' to circulate to surface.

Copeland Acid & Cement #30488

60/40 posmix with 4% gel

Perfs:

RECEIVED  
KCC DISTRICT #2  
APR 25 2006  
WICHITA, KS

RECEIVED  
MAY 01 2006  
KCC WICHITA

Remarks: CONTROL #2006-0015-001

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)