

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22161-00-02
Spot: NWSWSE Sec/Twnshp/Rge: 23-34S-35W
990 feet from S Section Line, 2280 feet from E Section Line
Lease Name: TAYLOR C Well #: 2
County: STEVENS Total Vertical Depth: 6670 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2950		WITH 2 SX CMT
CIBP		6380		WITH 2 SX CMT
PC		3200		CMT TO SURFACE
PROD	5.5	6627	0	WITH 625 SX CMT
SURF	8.625	1516		WITH 470 SX CMT

216.78

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/11/2006 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS THEN 25 SX CMT. MUD SPACER TO 1550' WITH 25 SX CMT. MUD SPACER TO 500' CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2006 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 400# HULLS WITH 25 SX CMT ON BOTTOM. 1ST PLUG PUMP MUD SPACER & 25 SX CMT AT 1550'. 2ND PLUG PUMP 65 SX CMT FROM 500' TO SURFACE AT 1500#. PUMP 5 SX CMT DOWN BACKSIDE.

Perfs:


Top	Bot	Thru	Comments
2718	2751		
2678	2696		
2652	2660		

INVOICED
DATE 5-1-06
REF. NO. 2006061570
RECEIVED
APR 27 2006
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT.

Plugged through: CSG

District: 01



Signed

Jim Holland (TECHNICIAN)

Form 216
PLA