

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01928-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 25-18S-8W  
985 feet from S Section Line, 3734 feet from E Section Line  
Lease Name: J R LANSING A Well #: 5  
County: RICE Total Vertical Depth: 3188 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 225 MAIN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	3165		250 SX CMT
SURF	10	210		150 SX CMT

\$110361

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/22/2006 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/22/2006 1:00 PM KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

Sanded perforations to 2750' and capped with 7 sacks of cement. Perforated at 1050', 700', and 260'. Ran tubing to 1050' and pumped 50 sacks of cement under pressure. Pulled tubing to 700' and pumped 50 sacks of cement at 400 psi. Pulled tubing to 260' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #22560

Log Tech #4463

**Perfs:**

Top	Bot	Thru	Comments
3007	3010		
2987	2997		
2983	2987		
2875	2879		
1396	1417		

RECEIVED  
KCC DISTRICT #2  
APR 17 2006  
WICHITA, KS

RECEIVED  
MAY 01 2006  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 5-1-06  
NO. 2006061578

ACT