

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01929-00-00
Spot: NENWSW Sec/Twnshp/Rge: 25-18S-8W
2282 feet from S Section Line, 4407 feet from E Section Line
Lease Name: LANSING J R - A Well #: 6
County: RICE Total Vertical Depth: 3229 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 225 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	3169		250 SX
SURF	8.625	198		85 SX

\$ 104.94

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2006 9:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 04/06/2006 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations and capped with 7 sacks of cement. Perforated at 1050', 700', and 250'. Ran tubing to 1050' and pumped 50 sacks of cement. Pulled tubing to 700' and pumped 50 sacks of cement. Pulled tubing to 250' and circulated cement to surface.

165 sacks of 60/40 posmix with 4% gel

Allied #24167

Perfs:

RECEIVED
KCC DISTRICT #2
APR 17 2006
WICHITA, KS

RECEIVED
MAY 01 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE

5-1-06

INV. NO.

2006061578

Form CP-2/3

PKT