

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-02232-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 27-19S-9W  
3656 feet from S Section Line, 1131 feet from E Section Line  
Lease Name: SEELY A Well #: 2  
County: RICE Total Vertical Depth: 3253 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 225 MAIN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3210		
PROD	5.5	3230		125 SX CMT
SURF	8.625	192		125 SX CMT

\$ 105.72

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/23/2006 2:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE  
Date/Time Plugging Completed: 03/23/2006 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2805' and capped with 5 sacks of cement. Perforated at 1150', 750', and 250'. Ran tubing to 1150' and pumped 35 sacks of cement. Pulled tubing to 750' and pumped 35 sacks of cement. Pulled tubing to 250' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #24133

Log Tech #4465

Perfs:

Top	Bot	Thru	Comments
2889	3146		

RECEIVED  
KCC DISTRICT #2  
APR 17 2006  
WICHITA, KS

RECEIVED  
MAY 01 2006  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 5-1-06

INVOICE NO. 20060615.78

PKT