

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20068-00-00
Spot: SENENE Sec/Twnshp/Rge: 25-18S-8W
4275 feet from S Section Line, 387 feet from E Section Line
Lease Name: SAM AINSWORTH Well #: 13
County: RICE Total Vertical Depth: 3212 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 225 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3212		300 sx
SURF	10	319		225 sx

\$ 104.39

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Sand perms to 2780' & ca; w/ 7 sxs cmt. Perf @ 1050', 700' & 370'. Run tbg to 1050' w/ 50 sxs cmt; pull tbg to 700' w/ 50 sxs cmt; pull tbg to 370' & circ cmt to surf.
Plugging Method:

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 03/15/2006 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2750' and capped with 7 sacks of cement. Perforated at 1050', 700', and 370'. Ran tubing to 1050' and pumped 50 sacks of cement at 500 psi. Pulled tubing to 700' and pumped 50 sacks of cement at 500 psi. Pulled tubing to 370' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #23522

Log Tech #4456

Perfs:

Top	Bot	Thru	Comments
3172	3178		
2954	2961		
2953	2960		
2839	2846		

RECEIVED
KCC DISTRICT #2
APR 17 2006
WICHITA, KS

RECEIVED
MAY 01 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE: 5-1-06
NO. 2006061578

PKT