

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02830-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 11-19S-10W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: OTT Well #: 3
County: RICE Total Vertical Depth: 2379 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3272		160 SX CMT
SURF	8.625	273		200 SX CMT

77.32

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2006 2:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/22/2006 4:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2790' and capped with 5 sacks of cement. Perforated at 1200', 850', and 330'. Ran tubing to 1200' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing to 330' and circulated cement to surface.

60/40 posmix with 4% gel

Log Tech #4464

Allied #22561

Perfs:

Top	Bot	Thru	Comments
3078	3086		
3020	3032		
2834	2840		

RECEIVED
KCC DISTRICT #2
APR 17 2006
WICHITA, KS

RECEIVED
MAY 01 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

5-1-06
20060615 79

AKG