

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21552-00-00
Spot: N2NENW Sec/Twnshp/Rge: 28-31S-8W
330 feet from N Section Line, 1980 feet from W Section Line
Lease Name: SCHMISSEUR A Well #: 1-28
County: HARPER Total Vertical Depth: 4412 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	211		

\$ 143.39

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/12/2006 4:00 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: GARY TALBOTT Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 04/12/2006 8:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Pumped 35 sacks of cement through drill pipe at 1350'. Pulled to 900' and pumped 35 sacks of cement. Pulled to 272' and pumped 35 sacks of cement. Pulled to 60' and pumped 25 sacks of cement to surface. Pumped 15 sacks of cement in rathole and pumped 10 sacks of cement in mousehole.

60/40 posmix with 4% gel

Allied #23713

Perfs:

RECEIVED
KCC DISTRICT #2
APR 17 2006
WICHITA, KS

INVOICED
DATE 5-1-06
TEL. NO. 20060615.73

RECEIVED
MAY 01 2006
KCC WICHITA

Remarks:

Plugged through: DP

District: 02

Signed Virgil Clothier
(TECHNICIAN)

(Handwritten signature)

(Handwritten initials)